BRUHATH BANGALORE MAHANAGARA PALIKE

Name of work: Estimate for providing and filling of potholes in ward No. 07- Byatarayanapura, Kodigehalli Sub Division.

2	Description of work	No.	Dimensions			Qty	Rate	Unit	Amount
			L	B	D				
1	2	3	4	5	6	7	8	9	10
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 141 / Item No. 19.1/ PWD SR 2015-16								
	Basic rate		77.00						
	Add A.W. 8%		6.16						
	Total		83.16						
	Talakaveri Layout								
	1st Main road- (near shobha mart)	1	2.50	2.50	0.10	0.63			
	Next to ICICI Bank Bdg	1	3.50	2.50	0.10	0.88			
	Opp to H NO.408, 1st main road	1	2.50	1.50	0.10	0.38			
	Shobha Sapphire Apt road								
	HNO.142 A	1	1.50	2.00	0.10	0.30			
	HNO.143	1	4.50	1.50	0.10	0.68			
	HNO.145	1	4.10	1.00	0.10	0.41			
	HNO.145	1	4.30	0.95	0.10	0.41			
	HNO.141	1	2.20	1.50	0.10	0.33			
	HNO.139	1	3.00	2.50	0.10	0.75			
	HNO.133	1	4.00	2.00	0.10	0.80			
	HNO.134	1	2.40	2.00	0.10	0.48			
	HNO.131&132	1	1.40	2.00	0.10	0.28			
	Patel's Callisto Apts Road, 2nd B Main								
	HNO.158	1	4.80	3.50	0.10	1.68			
	HNO.159	1	5.30	5.50	0.10	2.92			
	Opp Patel's Callisto Apts gate	1	1.20	4.10	0.10	0.49			
	HNO.163	1	3.00	2.50	0.10	0.75			
	HNO.163	1	1.00	1.00	0.10	0.10			
	HNO.163	1	2.00	1.00	0.10	0.20			
	Munigurappa Layout								
	Opp to Bhuvan Medical Store	1	2.50	3.60	0.10	0.90			
	Opp to Bhuvan Medical Store	1	2	1.5	0.1	0.3			
	Near J.K.Oil Store	1	3.5	1.5	0.1	0.525			
	Near J.K.Oil Store	1	1	1.3	0.1	0.13			
	HNO.124	1	1	1.5	0.1	0.15			
	HNO.124	1	2.5	2.1	0.1	0.525			
	Opp to SM Enterprises	1	2.6	1.2	0.1	0.312			
	Opp to Rajeshwari Mobile Accessories	1	2	1.5	0.1	0.3			

	Opp to Rajeshwari Mobile Accessories	1	2.5	1.3	0.10	0.33			
	Opp to Manjunath Bakery	1	3	1.3	0.10	0.39			
	Near to Manjunath Bakery	1	2.2	2	0.10	0.44			
	HNO.37	1	2	1	0.10	0.20			
	HNO.31/32	1	1.5	1.5	0.10	0.23			
	HNO.29/1	1	4.5	2.5	0.10	1.13			
	HNO.29/2	1	4	1.5	0.10	0.60			
	HNO.107/48	1	3	2.5	0.10	0.75			
	Near Madhu House Dead End	1	2	2.2	0.10	0.44			
	HNO.23&24	1	7.5	1.5	0.10	1.13			
	HNO.14	1	3	1.8	0.10	0.54			
	HNO.16	1	3	2	0.10	0.60			
	HNO.19	1	2	2.5	0.10	0.50			
	HNO.19	1	4	2	0.10	0.80			
	Opp to Govt Society	1	1.5	2	0.10	0.30			
	HNO.05	1	4.5	3.5	0.10	1.58			
	Beside Advocate Kumar House	1	4.5	1.5	0.10	0.68			
	Beside Advocate Kumar House	1	2.5	1.5	0.10	0.38			
	Kallappa Layout								
	Near Mico Krishnappa House	1	3.5	1.2	0.10	0.42			
	HNO.21A	1	1	1.35	0.10	0.14			
	HNO.80	1	8.5	2.5	0.10	2.13			
	Near Abhinay Tailor's	1	3.5	2.3	0.10	0.81			
	Behind Pachamma Temple, 3rd cross	1	4	1.8	0.10	0.72			
	Behind Pachamma Temple, 3rd cross	1	2.8	2.6	0.10	0.73			
	Behind Pachamma Temple, 3rd cross	1	1.5	1.5	0.10	0.23			
	HNO.78	1	4.6	1.2	0.10	0.55			
	Hoteppa Layout								
	HNO.4	1	2.3	1.5	0.10	0.35			
	HNO.19	1	1	1	0.10	0.10			
	Near Bhaskar House	1	3	2.1	0.10	0.63			
	Near Bhaskar House	1	2.6	2	0.10	0.52			
	Near BBMP Rajanna House	1	1	1.2	0.10	0.12			
	Bhadrappa Layout								
	Behind Bar Ramesh House Road	1	3	1.2	0.10	0.36			
	HNO.09	1	4.5	2.2	0.10	0.99			
	HNO.09	1	3	2	0.10	0.60			
	HNO.09	1	4.2	2	0.10	0.84			
	Munibhathappa House road	1	3	2.1	0.10	0.63			
	Munibhathappa House road	1	2.6	2	0.10	0.52			
	Munibhathappa House road	1	3.5	2	0.10	0.70			
	HNO.12	1	4.4	1.5	0.10	0.66			
	HNO.12	1	3.3	4	0.10	1.32			
	HNO.13	1	4.1	1	0.10	0.41			
	HNO.13	1	4.5	1.6	0.10	0.72			
	HNO.13	1	4.5	1.6	0.10	0.72			
	HNO.14	1	2.5	1.5	0.10	0.38			

	HNO.16	1	4.2	3.5	0.10	1.47			
	HNO.17	1	2	1.6	0.10	0.32			
	HNO.17	1	2	1.5	0.10	0.30			
	Venkategowda Layout 3rd Main Road								
	HNO.17	1	3	1.2	0.10	0.36			
	HNO.17	1	1	1.6	0.10	0.16			
	HNO.23	1	4	1.6	0.10	0.64			
	HNO.21	1	2.2	1	0.10	0.22			
	HNO.21	1	3	1.5	0.10	0.45			
	HNO.19A	1	3.5	1.6	0.10	0.56			
	HNO.31A	1	3.5	2.7	0.10	0.95			
	HNO.19	1	2.2	2	0.10	0.44			
	HNO.35	1	2	1.5	0.10	0.30			
	HNO.35	1	2	1.6	0.10	0.32			
	HNO.35	1	2	1.4	0.10	0.28			
	HNO.16A	1	3	1.1	0.10	0.33			
	HNO.38&39	1	1.5	1.3	0.10	0.20			
	HNO.16	1	2.7	1.2	0.10	0.32			
	HNO.15	1	2.2	1.6	0.10	0.35			
	HNO.15	1	2.7	1.3	0.10	0.35			
	HNO.40	1	1.6	1	0.10	0.16			
	HNO.41	1	2.8	0.9	0.10	0.25			
	HNO.42	1	1.5	3	0.10	0.45			
	HNO.12	1	1.4	1.2	0.10	0.17			
	HNO.43	1	2.6	2.1	0.10	0.55			
	HNO.10	1	1.1	1.1	0.10	0.12			
	HNO.8A	1	2.8	1.4	0.10	0.39			
	HNO.8	1	3	1.4	0.10	0.42			
	HNO.7	1	3.2	2	0.10	0.64			
	HNO.6	1	1	1	0.10	0.10			
	HNO.5	1	3	1.5	0.10	0.45			
	HNO.53	1	1.6	1.2	0.10	0.19			
	HNO.53	1	2.2	1	0.10	0.22			
	HNO.53	1	4	1	0.10	0.40			
	HNO.54	1	2.8	1.4	0.10	0.39			
	HNO.56	1	4.3	1	0.10	0.43			
	HNO.6/1	1	2.6	2.2	0.10	0.57			
	Venkategowda Layout 2nd Main Road								
	Beside Ayyappa Temple	1	4	3	0.10	1.20			
	HNO.40B	1	4.6	3.5	0.10	1.61			
	HNO.40B	1	3.1	1.4	0.10	0.43			
	HNO.2	1	7.2	1.4	0.10	1.01			
	HNO.2	1	3.5	1.4	0.10	0.49			
	HNO.2	1	1.1	2.1	0.10	0.23			
	HNO.3	1	2.6	1.3	0.10	0.34			
	HNO.3	1	2.5	1.1	0.10	0.28			
	HNO.3	1	1.1	1.5	0.10	0.17			
	HNO.3	1	1.5	1.6	0.10	0.24			
	HNO.3	1	4.2	1.3	0.10	0.55			
	HNO.3	1	1.3	1.6	0.10	0.21			
	HNO.3	1	1.6	1	0.10	0.16			
	HNO.3	1	1.5	1.1	0.10	0.17			
	HNO.3	1	1.1	1.1	0.10	0.12			

	HNO.3	1	4.1	2.3	0.10	0.94			
	HNO.4	1	4.6	1	0.10	0.46			
	HNO.3	1	3.7	0.7	0.10	0.26			
	HNO.37/B	1	2.1	2.7	0.10	0.57			
	HNO.37/A	1	5.2	1.9	0.10	0.99			
		1	2.4	1	0.10	0.24			
	HNO.36	1	2.1	1.1	0.10	0.23			
	HNO.35/B	1	1.8	0.9	0.10	0.16			
	HNO.35/A	1	1.1	1.2	0.10	0.13			
	HNO.34	1	2.3	2.6	0.10	0.60			
	HNO.8	1	3.1	1.4	0.10	0.43			
	HNO.8	1	2	1.4	0.10	0.28			
	HNO.8	1	2.1	1.1	0.10	0.23			
	HNO.9	1	2	2.7	0.10	0.54			
	HNO.9	1	3.5	2.1	0.10	0.74			
	HNO.32	1	2	1.1	0.10	0.22			
	HNO.10	1	4	2	0.10	0.80			
	HNO.31	1	1.8	1	0.10	0.18			
	HNO.31	1	4	2	0.10	0.80			
	HNO.11	1	3.8	1.7	0.10	0.65			
	HNO.12	1	3	1.5	0.10	0.45			
	HNO.12	1	2.4	1	0.10	0.24			
	HNO.29	1	2.1	1.1	0.10	0.23			
	HNO.29	1	1.6	1.4	0.10	0.22			
	HNO.29	1	2.1	1.1	0.10	0.23			
	HNO.28&29	1	3.7	1.6	0.10	0.59			
	HNO.27/A	1	3.9	1.4	0.10	0.55			
	HNO.27/A	1	4.7	1.1	0.10	0.52			
	HNO.27/A	1	4.7	2	0.10	0.94			
	HNO.15	1	3	1.4	0.10	0.42			
	HNO.15	1	2	1	0.10	0.20			
	HNO.15	1	2.2	1	0.10	0.22			
	HNO.24	1	1.4	1.6	0.10	0.22			
	HNO.24	1	2.4	1.2	0.10	0.29			
	HNO.17	1	4.5	1.1	0.10	0.50			
	HNO.17	1	4.9	2.9	0.10	1.42			
	HNO.18/A	1	2.4	1	0.10	0.24			
	HNO.18/B	1	3	1.3	0.10	0.39			
	HNO.22	1	3	1.5	0.10	0.45			
	HNO.22	1	3.6	1.3	0.10	0.47			
	HNO.21 A	1	1.3	2.3	0.10	0.30			
	HNO.22	1	4.5	1.4	0.10	0.63			
	HNO.20	1	1.5	1.4	0.10	0.21			
	HNO.19	1	2.1	3.5	0.10	0.74			
	HNO.19	1	3.5	1.9	0.10	0.67			
	HNO.19	1	2.6	1.9	0.10	0.49			
	Venkategowda Layout 1st Main Road								
	Opp to Aadi Byraveshwara shop	1	2.2	1.5	0.10	0.33			
	HNO.54	1	3.5	1	0.10	0.35			
	HNO.54	1	5.2	1.1	0.10	0.57			
	HNO.27	1	1.6	1.8	0.10	0.29			
	Near New Construction Bldg	1	3.6	2.4	0.10	0.86			
	Near New Construction Bldg	1	2.9	1.1	0.10	0.32			

	HNO.15	1	2.1	3.7	0.10	0.78			
	HNO.15	1	11.4	1.6	0.10	1.82			
	HNO.11	1	1	0.8	0.10	0.08			
	HNO.09	1	2.6	2.5	0.10	0.65			
	HNO.09	1	1.7	1.3	0.10	0.22			
	HNO.09	1	1.4	1.1	0.10	0.15			
	HNO.09	1	2.4	2	0.10	0.48			
	HNO.45	1	1.1	1.3	0.10	0.14			
	HNO.45	1	1.6	1.4	0.10	0.22			
	HNO.45	1	6.9	2.5	0.10	1.73			
	HNO.7	1	1.5	1.6	0.10	0.24			
	HNO.7	1	6.8	2.1	0.10	1.43			
	HNO.52	1	3.7	3	0.10	1.11			
	HNO.52	1	3.1	1.3	0.10	0.40			
	HNO.2 & 53	1	1	1.8	0.10	0.18			
	HNO.2 & 53	1	2.7	1.2	0.10	0.32			
	HNO.2 & 53	1	11	2.6	0.10	2.86			
	HNO.1 & 53	1	2.7	1.1	0.10	0.30			
	HNO.1	1	3.8	3.7	0.10	1.41			
	HNO.1	1	3.8	1.5	0.10	0.57			
	HNO.1 & 54	1	3.8	1.1	0.10	0.42			
	HNO.1 & 54	1	3.9	1.9	0.10	0.74			
	HNO.20	1	7.3	2.5	0.10	1.83			
	Venkategowda Layout 1st B Main Road								
	HNO.11	1	8	8	0.10	6.40			
	HNO.32	1	5.6	2.2	0.10	1.23			
	HNO.27	1	3.6	1.3	0.10	0.47			
	HNO.28	1	3.7	1	0.10	0.37			
	HNO.29	1	3.4	3.7	0.10	1.26			
	HNO.30	1	1.3	3.4	0.10	0.44			
	HNO.30	1	1.3	2.7	0.10	0.35			
	HNO.15	1	3.7	1.1	0.10	0.41			
	HNO.11	1	4.5	2.1	0.10	0.95			
	HNO.184	1	4	1.3	0.10	0.52			
	HNO.1	1	5	1.3	0.10	0.65			
	HNO.1	1	3.5	1.2	0.10	0.42			
	HNO.1	1	5.1	1.4	0.10	0.71			
	HNO.2	1	2.1	1.3	0.10	0.27			
	HNO.3	1	2.3	1.3	0.10	0.30			
	HNO.3	1	3	1.7	0.10	0.51			
	HNO.3	1	4.4	1.3	0.10	0.57			
	HNO.5	1	4.1	1.4	0.10	0.57			
	HNO.5	1	1.1	1.3	0.10	0.14			
	HNO.6	1	3.8	0.8	0.10	0.30			
	HNO.6	1	3.1	1	0.10	0.31			
	HNO.3	1	4.2	2	0.10	0.84			
	HNO.3	1	2	2	0.10	0.40			
	HNO.8	1	2.3	1.3	0.10	0.30			
	HNO.9	1	2.8	1.6	0.10	0.45			
	HNO.53A	1	6	0.8	0.10	0.48			
	HNO.7/8	1	1.4	1.2	0.10	0.17			
	Venkategowda Layout 1st A Main Road								

	Main road of Pampa Extension & Venkategowda	1	2.4	3.3	0.10	0.79			
	Main road of Pampa Extension & Venkategowda	1	1.8	2.3	0.10	0.41			
	Main road of Pampa Extension & Venkategowda	1	1.8	1.8	0.10	0.32			
	HNO.59B	1	3.1	2	0.10	0.62			
	HNO.42	1	1.8	1.8	0.10	0.32			
	HNO.30	1	2.5	2.7	0.10	0.68			
	HNO.19	1	3.7	2.8	0.10	1.04			
	HNO.19/1	1	1.8	1.2	0.10	0.22			
	HNO.19/1	1	2.7	2.7	0.10	0.73			
	HNO.12	1	2.6	2.1	0.10	0.55			
	HNO.9	1	1.2	0.8	0.10	0.10			
	3RD CROSS PAMPA EXTENSION								
	BESIDE FAIR PEARL APTS	1	1.5	2.2	0.10	0.33			
	4TH CROSS PAMPA EXTENSION								
	HNO.12&11	1	1.5	1.5	0.10	0.23			
	HNO.12&11	1	3.2	3.1	0.10	0.99			
	4TH CROSS	1	5	1.6	0.10	0.80			
	4TH CROSS	1	2	1.2	0.10	0.24			
	4TH CROSS	1	5.1	3.6	0.10	1.84			
	4TH CROSS	1	6	2.3	0.10	1.38			
	5TH CROSS PAMPA EXTENSION								
	HNO.16/2	1	6.3	2.4	0.10	1.51			
	HNO.20,3rd mainroad, pampa extn	1	1.5	0.9	0.10	0.14			
	HNO.20,3rd mainroad, pampa extn	1	4	1	0.10	0.40			
	HNO.19,3rd mainroad, pampa extn	1	4	2	0.10	0.80			
	HNO.19,3rd mainroad, pampa extn	1	4	1	0.10	0.40			
	HNO.207	1	5	1	0.10	0.50			
	HNO.207	1	3.1	1	0.10	0.31			
	HNO.207	1	5.2	1	0.10	0.52			
	HNO.207	1	3.3	1.5	0.10	0.50			
	HNO.207	1	30	1.2	0.10	3.60			
	HNO.41	1	4	1.5	0.10	0.60			
	HNO.41	1	4	1	0.10	0.40			
	center of 4th mainroad	1	3	2	0.10	0.60			
	center of 5th mainroad	1	4	2.7	0.10	1.08			
	center of 5th mainroad	1	2	1.5	0.10	0.30			
	HNO.65,5th cross	1	3	1.2	0.10	0.36			
	HNO.66,5th cross	1	1.6	1.5	0.10	0.24			
	HNO.67,5th main	1	3	2.2	0.10	0.66			
	HNO.29,5th main	1	2	1.5	0.10	0.30			
	HNO.25,5th main	1	2.5	1	0.10	0.25			
	HNO.23 & 24,5th main	1	13	4	0.10	5.20			
	HNO.22,5th main	1	4	1	0.10	0.40			
	HNO.22,5th main	1	2	1	0.10	0.20			
	HNO.22,5th main	1	1	0.6	0.10	0.06			

	HNO.20,5th main	1	2.2	1.3	0.10	0.29			
	HNO.19,5th main	1	4	1.2	0.10	0.48			
	HNO.19,5th main	1	1.6	1.1	0.10	0.18			
	HNO.19,5th main	1	4	1	0.10	0.40			
	HNO.46,5th main	1	4	1.2	0.10	0.48			
	HNO.47,5th main	1	3	3	0.10	0.90			
	HNO.49,5th main	1	3.3	1.5	0.10	0.50			
	HNO.3,13th cross pampa extn	1	3.4	1.8	0.10	0.61			
	HNO.6,13th cross pampa extn	1	2.2	1	0.10	0.22			
	HNO.7,13th cross pampa extn	1	5	2.2	0.10	1.10			
	HNO.12,13th cross pampa extn	1	7.5	1.5	0.10	1.13			
	12th cross pampa extn	1	5	2.2	0.10	1.10			
	HNO.24,12th cross pampa extn	1	1	1.5	0.10	0.15			
	11th cross pampa extn Corner House	1	6	1.2	0.10	0.72			
	HNO.40,11th cross pampa extn	1	8	1.5	0.10	1.20			
	Pampa Extn MainRoad	1	1.2	3.6	0.10	0.43			
	Pampa Extn MainRoad	1	1.6	1	0.10	0.16			
	Pampa Extn MainRoad	1	2.6	1.7	0.10	0.44			
	9th cross ,Pampa Extn	1	3	3	0.10	0.90			
	9th cross ,Pampa Extn	1	2.7	1.3	0.10	0.35			
	HNO.57	1	4	0.9	0.10	0.36			
	HNO.56	1	2	0.8	0.10	0.16			
	HNO.12	1	5	0.6	0.10	0.30			
	HNO.04	1	1.6	1	0.10	0.16			
	Chiranjeevi Layout								
	HNO.19,2nd A Main	1	5.2	0.8	0.10	0.42			
	HNO.31,2nd A Main	1	1	0.6	0.10	0.06			
	HNO.13,2nd A Main	1	7.4	0.6	0.10	0.44			
	Vidyaniketan School Road Opp 2nd A Main Entrance	1	3.1	2.2	0.10	0.68			
	Opp Vidyaniketan School Gate	1	15	3	0.10	4.50			
	HNO.66,5th cross	1	1.3	0.8	0.10	0.10			
	Opp to Rock on Fashions Shop	1	0.8	0.8	0.10	0.06			
	Opp to Rock on Fashions Shop	1	1.3	0.8	0.10	0.10			
	Opp to Rock on Fashions Shop	1	2.2	1.4	0.10	0.31			
	Opp to Rock on Fashions Shop	1	0.7	0.8	0.10	0.06			
	Opp to Rock on Fashions Shop	1	1.6	1	0.10	0.16			
	Opp to Rock on Fashions Shop	1	2.3	2	0.10	0.46			
	Opp to Manjunatha Tiffin Center, Vrindavan Apts road	1	1	1	0.10	0.10			

	Opp to Manjunatha Tiffin Center, Vrindavan Apts road	1	0.8	0.8	0.10	0.06			
	HNO.67	1	3.4	2.1	0.10	0.71			
	HNO.15/1, Vrindavan Apts road	1	1.6	1.7	0.10	0.27			
	HNO.15/1, Vrindavan Apts road	1	3.1	2.4	0.10	0.74			
	HNO.13,32/1/13	1	3	1.2	0.10	0.36			
	Muniswamy gowda Layout Main road	1	2	1	0.10	0.20			
	Muniswamy gowda Layout Main road	1	2	1	0.10	0.20			
	HNO.07, Kempapura MainRoad	1	1	0.7	0.10	0.07			
	HNO.07, Kempapura MainRoad	1	13	3	0.10	3.90			
	HNO.07, Kempapura MainRoad	1	3	2	0.10	0.60			
	HNO.07, Kempapura MainRoad	1	1	1	0.10	0.10			
	HNO.07, Kempapura MainRoad	1	15	2.5	0.10	3.75			
	4th Mainroad, Coffee Board Layout	1	6	1	0.10	0.60			
	HNO.194,Opp to Vaibhav Residency, Coffee Board Layout	1	7	0.9	0.10	0.63			
	Opp to HDFC Bank, Coffee Board Layout	1	6	3.3	0.10	1.98			
	HNO.15, Gopalappa Layout	1	3.5	0.8	0.10	0.28			
	HNO.30, Gopalappa Layout	1	1	1	0.10	0.10			
	HNO.30, Gopalappa Layout	1	2	1	0.10	0.20			
	Coffee Board Layout Main Road via Gopalappa Layout	1	3	1	0.10	0.30			
	Coffee Board Layout Main Road via Gopalappa Layout	1	4.5	3	0.10	1.35			
	Coffee Board Layout Park Beside Road	1	1.5	1	0.10	0.15			
	5th Cross Coffee Board Layout,	1	1	1	0.10	0.10			
	5th Cross, 8th mainroad Coffee Board Layout,	1	6	1	0.10	0.60			
	Beside Ram Mandira Road, Coffee Board layout	1	5	1	0.10	0.50			
	3rd mainroad Coffee Board Layout,	1	4.8	2.3	0.10	1.10			
	HNO.280, 5th cross, Coffee Board Layout	1	4	1	0.10	0.40			
	Veerannapalya								
	Maruthi Sweing Machine	1	1	1	0.10	0.10			
	Railway Gate	1	6.5	2	0.10	1.30			
	Railway Gate	1	5	2	0.10	1.00			
	Temple	1	3	3	0.10	0.90			
	Temple	1	6	1	0.10	0.60			
	Ganga Interior	1	2	2	0.10	0.40			

	Ganga Interior	1	1.5	1	0.10	0.15			
	Axis Bank Atm	1	1	1	0.10	0.10			
	Electric Pole	1	1	1	0.10	0.10			
	Transformer	1	1	1.7	0.10	0.17			
	Euro Kids	1	2	1	0.10	0.20			
	Euro Kids	1	5	1.5	0.10	0.75			
	Provision Store	1	1	1	0.10	0.10			
	Ashraya Trust	1	3	2	0.10	0.60			
	Ashraya Trust	1	1	1	0.10	0.10			
	Ashraya Trust	1	2	1	0.10	0.20			
	Ashraya Trust	1	1	1	0.10	0.10			
	Ashraya Trust	1	1	1	0.10	0.10			
	Ashraya Trust	1	1	1	0.10	0.10			
	Paragon Shop	1	1	1	0.10	0.10			
	Hotel Bangalore	1	7	1	0.10	0.70			
	Siri Lake View	1	11	6	0.10	6.60			
	HNO 65/54-3-1	1	12	6	0.10	7.20			
	MES PHARMACY	1	9	3	0.10	2.70			
	SERVICE ROAD	1	2	6	0.10	1.20			
	1st cross. Near Anjenaya Temple	1	2	1	0.10	0.20			
		1	8.9	1.8	0.10	1.60			
	2nd B cross								
	HNO 84. Brahma lingaeshwari co	1	3	2	0.10	0.60			
	No.49 opp	1	1.5	1.6	0.10	0.24			
	3rd B cross corner	1	2.5	1.6	0.10	0.40			
	4th b cross opp to H NO. 156	1	4.3	4	0.10	1.72			
		1	3.5	3	0.10	1.05			
	Jakkur layout main road								
	H NO.193 Sri krishna enterprises	1	3	2	0.10	0.60			
	H NO.243 OPP	1	2.6	1.5	0.10	0.39			
		1	2	1.8	0.10	0.36			
		1	1.5	1.35	0.10	0.20			
	5 TH B CROSS CORNER	1	2.5	3	0.10	0.75			
	182 OPP	1	2.5	2	0.10	0.50			
	6TH B CROSS								
	HNO 252	1	7.5	2.8	0.10	2.10			
	H NO 199	1	2.3	2	0.10	0.46			
	H NO 514	1	3.5	1.5	0.10	0.53			
	H NO 5	1	3.1	1.5	0.10	0.47			
	7TH B CROSS								
	H NO 02OPP	1	3.8	1.6	0.10	0.61			
	H NO 297 OPP	1	1.6	1.8	0.10	0.29			
	H NO 304 OPP	1	2	2.5	0.10	0.50			
	H NO 513 OPP	1	1.5	1.5	0.10	0.23			
	DEEPAK NILAYA OPP	1	2	2.5	0.10	0.50			
		1	1.5	2	0.10	0.30			
		1	1.6	2.6	0.10	0.42			
		1	1.5	1.5	0.10	0.23			
	9TH CROSS B								
	H NO 218/14 OPP	1	1.5	1.5	0.10	0.23			
		1	1.5	1.5	0.10	0.23			
		1	1.5	1.5	0.10	0.23			
		1	4.5	1.3	0.10	0.59			
	H NO 13/1 OPP	1	2.7	1.4	0.10	0.38			
	11TH CROSS B					0.00			

	Ayyappa temple opp	1	4.8	1.2	0.10	0.58			
	H NO 463 OPP	1	7.5	1.7	0.10	1.28			
	H NO 418 OPP	1	1.7	1.1	0.10	0.19			
		1	1.8	1.8	0.10	0.32			
	H NO 418 OPP	1	3.8	1.5	0.10	0.57			
		1	2.3	1.1	0.10	0.25			
	H NO 395 OPP	1	1	1	0.10	0.10			
	H NO 424 OPP	1	4.3	1.1	0.10	0.47			
		1	1.8	1.5	0.10	0.27			
	9th A CROSS- Shiva shree cndime	1	3.7	3.1	0.10	1.15			
	H NO 374 OPP 8th A cross	1	5.2	1.1	0.10	0.57			
	H NO 333	1	5.2	3.1	0.10	1.61			
	7th A cross	1	1	1	0.10	0.10			
	Ganesha temple opp	1	1.5	1.2	0.10	0.18			
		1	4.1	1.1	0.10	0.45			
	BGN School opp	1	17.3	1.1	0.10	1.90			
	H NO 268	1	3.2	1	0.10	0.32			
	6th A cross								
	H NO 272	1	2.1	1.5	0.10	0.32			
	5th A cross	1	2.5	1.1	0.10	0.28			
	H NO 195	1	3.5	1.5	0.10	0.53			
		1	3.5	1.5	0.10	0.53			
	H NO 202	1	2.2	1.5	0.10	0.33			
	H NO 228 opp	1	1.8	0.9	0.10	0.16			
		1	1	1	0.10	0.10			
	4th A cross								
	H NO 224 med plus opp	1	4.1	2.2	0.10	0.90			
		1	3.5	1	0.10	0.35			
	H NO 217 opp	1	2.6	1	0.10	0.26			
		1	8.9	0.8	0.10	0.71			
		1	3.3	3.3	0.10	1.09			
	3th A cross								
	H NO 137 opp	1	1	1	0.10	0.10			
	H NO 136 opp	1	5.8	5.1	0.10	2.96			
		1	2.3	1.2	0.10	0.28			
		1	1	1	0.10	0.10			
		1	2.4	1.8	0.10	0.43			
		1	1.8	1.8	0.10	0.32			
	H NO 119 opp	1	2.8	1.66	0.10	0.46			
		1	1.7	1.6	0.10	0.27			
	H NO 118	1	3.1	2.1	0.10	0.65			
	Checken centre	1	6.1	1.2	0.10	0.73			
	2nd A Cross								
	H NO 08 opp	1	2.9	1.5	0.10	0.44			
	H NO 33	1	4.1	1.1	0.10	0.45			
		1	1	1	0.10	0.10			
	1st A cross								
	H NO 08 opp	1	2.9	1.5	0.10	0.44			
		1	2.9	1.1	0.10	0.32			
	H N0 15 Opp	1	9.1	1.5	0.10	1.37			
	12th cross								
	H N0 442 opp	1	3.5	2.1	0.10	0.74			
	H N0 429 opp	1	2.9	1.4	0.10	0.41			
	H N0 429 opp	1	2.5	1.5	0.10	0.38			
	H N0 436 opp	1	1	1	0.10	0.10			

	H N0 436 opp	1	2.6	1.4	0.10	0.36			
	H N0 416 opp	1	4.8	2.1	0.10	1.01			
	13th A cross								
		1	3.2	1.1	0.10	0.35			
		1	2.1	1.4	0.10	0.29			
		1	2.3	1.1	0.10	0.25			
		1	5.7	1.1	0.10	0.63			
		1	4.4	0.9	0.10	0.40			
	14th Cross	1	12.3	0.4	0.10	0.49			
	15th cross	1	2	1	0.10	0.20			
	16th cross								
	H N0 487	1	2.8	1.5	0.10	0.42			
	H N0 28/A	1	3.1	6.1	0.10	1.89			
	18th cross	1	2.5	3.1	0.10	0.78			
	Opp to santhosh vihar	1	5.2	1.1	0.10	0.57			
	Sahakara Nagara								
	1st cross G block								
	H No 23 opp	1	13.7	5.1	0.10	6.99			
	H No 34 opp	1	4.9	1.3	0.10	0.64			
	H No 33 opp	1	5.9	1	0.10	0.59			
	2nd cross G block								
	H No 37 opp	1	4.8	1.4	0.10	0.67			
	H No 37/1	1	4.5	1.6	0.10	0.72			
	H No 36/3	1	4.6	1.5	0.10	0.69			
	H No 36/4	1	5.1	1	0.10	0.51			
	H No 37/6	1	5.4	5	0.10	2.70			
	H No 111	1	1.7	1.6	0.10	0.27			
	H No 108	1	2.1	1.4	0.10	0.29			
	H No 195	1	7.1	1	0.10	0.71			
	8th cross 20th main								
	H No 97	1	1	1	0.10	0.10			
	9th cross 17th main								
	H No 87	1	6.1	1	0.10	0.61			
	11th cross 18th main					0.00			
	ramp	1	3.6	2.3	0.10	0.83			
	H No 459	1	4.9	2.3	0.10	1.13			
	13th cross 18th main E Block H No 415	1	5.8	1.5	0.10	0.87			
	14th main F block								
	Near Canara Bank	1	6.2	1	0.10	0.62			
	F 536	1	7.2	1	0.10	0.72			
		1	3.7	1.1	0.10	0.41			
	H No. 539 opp	1	5.5	1	0.10	0.55			
	H No. 423opp	1	5	1	0.10	0.50			
	60 ft road near Sangeetha show r	1	1	1	0.10	0.10			
	H No 494 opp	1	2	2.4	0.10	0.48			
		1	2.8	2.6	0.10	0.73			
	H No 512	1	3.6	3.2	0.10	1.15			
	E block 6th 14th main H NO 2617	1	4.7	1	0.10	0.47			
	E block 6th 14th main H NO 2619	1	3.8	1	0.10	0.38			
	e block 6ht 14th main H No.2633	1	6.6	1	0.10	0.66			
	sbh	1	4.3	1	0.10	0.43			
	E Block 3rd cross 14th main H Nc	1	2.8	1	0.10	0.28			
		1	2.1	1.5	0.10	0.32			

	G Block more back side	1	3.5	3.3	0.10	1.16			
		1	2.2	1.2	0.10	0.26			
		1	3.9	1.9	0.10	0.74			
		1	4.5	1	0.10	0.45			
		1	2.1	1.1	0.10	0.23			
	6th cross 13th main E block corne	1	3.1	2.1	0.10	0.65			
	2589/1	1	5.6	1.7	0.10	0.95			
	7th cross 13th main E Block HNO	1	4.4	1	0.10	0.44			
	9th cross E Block H No 2478	1	6.9	2	0.10	1.38			
	15th cross 5ht main A block	1	5.9	1	0.10	0.59			
	H No 848 A block	1	7.1	8.1	0.10	5.75			
		1	3.5	4	0.10	1.40			
	H No 823 opp	1	4.2	4	0.10	1.68			
	Library	1	2.1	1	0.10	0.21			
	16th 20th main	1	1.4	1.2	0.10	0.17			
	19th 14th Ganesha templemroad	1	5.1	1.1	0.10	0.56			
		1	5.1	1	0.10	0.51			
	H No 797 opp	1	7	2	0.10	1.40			
		1	2.1	1.1	0.10	0.23			
	19th cross 16th main H no 728	1	5.1	1	0.10	0.51			
	H No 726	1	5.5	1	0.10	0.55			
	H No 702	1	4.1	3	0.10	1.23			
	H No 716	1	1	1	0.10	0.10			
	H No 713	1	7.1	1	0.10	0.71			
	H No 610	1	1.5	1.5	0.10	0.23			
	H No 611	1	1.5	1.1	0.10	0.17			
	H No 612	1	4.5	1	0.10	0.45			
	19th cross 17th main A H No 687	1	4.1	3	0.10	1.23			
	H No 665	1	5.1	1	0.10	0.51			
	16th cross 18th main H NO 656	1	5.1	1	0.10	0.51			
		1	5.9	1	0.10	0.59			
	20th cross 23 main H No 1063	1	3.1	1	0.10	0.31			
		1	6	1.1	0.10	0.66			
	H No 1049	1	5	1	0.10	0.50			
	Railway main road	1	2.1	1.2	0.10	0.25			
		1	3.1	1.5	0.10	0.47			
	H No 1056/2	1	5.3	3.3	0.10	1.75			
	23 rd 19th main A Hno 1183/5	1	6.1	1	0.10	0.61			
	20th cross 15th main Hno 754	1	6.1	1	0.10	0.61			
	H No 1339	1	5.5	1	0.10	0.55			
	H No 1295	1	6.1	1	0.10	0.61			
		1	6.1	1	0.10	0.61			
	Amruthanagara A sector					0.00			
	Muneshwara TeMPLE ROAD 1stc	1	8	1.5	0.10	1.20			
		1	2	1.5	0.10	0.30			
	H No 17 2nd cross road	1	3	2	0.10	0.60			
	2nd cross	1	2	2	0.10	0.40			
		1	2	2	0.10	0.40			
	H NO 2nd cross	1	2.5	2.5	0.10	0.63			
		1	1	2.3	0.10	0.23			
	4th A cross	1	4.5	2	0.10	0.90			
	1 A cross	1	2.5	2.6	0.10	0.65			
	H No 17	1	2	2	0.10	0.40			
		1	1.5	1.5	0.10	0.23			
	H No 7	1	4	2.5	0.10	1.00			

		1	3.5	1.5	0.10	0.53			
	H No 8 A	1	2	2	0.10	0.40			
		1	2	1.8	0.10	0.36			
	H No 27	1	7	1.8	0.10	1.26			
	2nd cross	1	4.5	1	0.10	0.45			
	3rd cross road	1	4.5	10.5	0.10	4.73			
	H No 20 B cross	1	3.3	3.2	0.10	1.06			
	H NO 20	1	5.2	2.5	0.10	1.30			
		1	4.5	4.5	0.10	2.03			
	H No 726	1	1.5	1.5	0.10	0.23			
	3rd cross road	1	6	3.5	0.10	2.10			
	5th cross road	1	10	1.5	0.10	1.50			
	H nO 43	1	4	3	0.10	1.20			
	h nO 5	1	2	2.5	0.10	0.50			
		1	3.5	1.5	0.10	0.53			
		1	3	1.8	0.10	0.54			
		1	2	2	0.10	0.40			
	H NO 85 3rd main	1	4	2	0.10	0.80			
	Kempapura main road	1	5.5	2	0.10	1.10			
		1	5	3	0.10	1.50			
		1	3	3.2	0.10	0.96			
		1	3.15	3	0.10	0.95			
		1	5	1.5	0.10	0.75			
		1	3.5	1.5	0.10	0.53			
	Kuvempu layout	1	4.5	3	0.10	1.35			
		1	5.5	2.5	0.10	1.38			
		1	5	2	0.10	1.00			
		1	4.5	2	0.10	0.90			
		1	6	2.5	0.10	1.50			
		1	5	2	0.10	1.00			
		1	3	2.5	0.10	0.75			
					Total:-	**372.48**	83.16	Cum	30976.00
2	KSSRB M 400-17: Providing laying, spreading and compacting graded fine aggregate to wet mix macadam specificationns including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surfce and compating with vibratory roller to achieve the desired density complete as per specifications. MORTH specifications no. 406(P-157., It No: 20.18)								
	Basic rate		1587.00						
	Add A.W. 8%		126.96						
	Total		1713.96						
	Qty vide Item No 1			3633	0.1	363.3038			
					Total:-	**363.30**	1713.96	Sqm	622689.00

3	Filling pot holes and patch repairs with bituminous concrete 40mm. SRRB M3000-5.Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.30, back filling the potholes with hot bituminous materail as per clause 500.4, compacting, trimming and finishing the surface to form a smooth continous surface all as per clause 3004-2, complete as per specifications, MORTH specifications No.3004-2. (Page No. 250 and item No. 35.5) SR-2015-16								
	Basic rate		~~343.00~~	283.00					
	Add A.W. 8%		~~27.44~~	22.64					
	Total		~~370.44~~	305.64		3633.00			
	Qty vide Item No 1					~~3205~~.50	305.64		1110402.00
					Total:-	**~~3205.50~~**	~~370~~.44	Sqm	1187446.00 -
	Sub total						1764067.00		1763513.00
									176407.67
5	Add 1% third party inspection charges								17635.13
6	Miscellaneous and rounding off								~~851.87~~ 292.33
							Total:-		**1782000.00**

Certificate:-

1)This is certified that the work spot comes under BBMP limits only.

2)The rates are as per CSR of 2015-16 year of PWD Bangalore Circle.

3)The Provisions made in estimate are adequate and necessary.

Asst.Engineer N.D.

Ward no.7

Asst.Exe.Engineer

Kodigehalli Sub-division

B.B.M.P.

Executive Engineer. 3/11/16.

Byatrayanapura Division

B.B.M.P.

Administrative Approval

Accorded For 17.82 lakhRs

Head of A/C..... P-1771

CER NO :..... 52 **Dt:** 23-11-16

TA CE (YNK)

Technical Sanction

Accorded For 17.82 lakhRs

Head of A/C..... P-1771

CER NO :..... 72 **Dt:** 23.11.16

TA CE (YNK)